

NOTES:

- DES ENGINEERING MUST SPOT SERVICE POLE LOCATION PRIOR TO POLE INSTALLATION
- 2. IF SERVICE IS MORE THAN I-FOOT FROM SIDE OF MOBILE HOME, CONDUIT BETWEEN POLE AND MOBILE HOME MUST BE BURIED
- ALL WIRING MUST COMPLY WITH ALL LOCAL, STATE, AND NATIONAL ELECTRICAL CODES
- 4. THE MOBILE HOME SERVICE EQUIPMENT SHALL BE LOCATED ADJACENT TO AND NOT MORE THAN 12 INCHES FROM THE MOBILE HOME
- 5. THE EQUIPMENT SHALL NOT BE MOUNTED ON THE MOBILE HOME UNLESS HOME IS ON A PERMANENT CONCRETE BLOCK FOUNDATION
- 6. WIRE AND CONDUIT TO BE SIZED ACCORDING TO SIZE OF SERVICE PER NEC



DYERSBURG ELECTRIC SYSTEM

OVERHEAD MOBILE HOME SPECIFICATIONS