

NOTES:

- DES ENGINEERING MUST SPOT METER POLE LOCATION PRIOR TO POLE INSTALLATION
- 2. ALL WIRING MUST COMPLY WITH ALL LOCAL, STATE, AND NATIONAL ELECTRICAL CODES
- 3. THE MOBILE HOME SERVICE EQUIPMENT SHALL BE LOCATED ADJACENT TO AND NOT MORE THAN 12 INCHES FROM THE MOBILE HOME. WIRE AND CONDUIT TO BE SIZED ACCORDING TO SIZE OF SERVICE PER NEC
- 4. THE EQUIPMENT SHALL NOT BE MOUNTED ON THE MOBILE HOME, UNLESS HOME IS ON A PERMANENT CONCRETE BLOCK FOUNDATION
- 5. CUSTOMER SHALL OPEN & CLOSE A 36" DEEP TRENCH, THAT IS FREE OF DEBRIS & NO STANDING WATER, FROM METER BASE TO POINT OF CONNECTION.
- 6. TRENCH MUST HAVE AN OPENING AT EACH END LARGE ENOUGH FOR A PERSON TO WORK IN.
- DES REQUIRES A 24HR NOTICE PRIOR TO OPENING OF TRENCH.



DYERSBURG ELECTRIC SYSTEM

UNDERGROUND MOBILE HOME SPECIFICATIONS